



NOTES

1. THE ENTIRE EXTENTS OF THE EXCAVATED TRENCH SHALL BE BACKFILLED WITH 1"-0 CRUSHED AGGREGATE TO FINISHED GRADE. SEE STANDARD DRAWING NO. 205.
2. MINIMUM 36" COVER OVER PIPE REQUIRED

CITY OF ALBANY, OREGON
PUBLIC WORKS DEPARTMENT

STANDARD SANITARY SEWER/STORM
DRAIN MAINLINE CLEANOUT DETAIL

NO SCALE

JANUARY 2015

NO. 416