



NOTES

1. THE ENTIRE EXTENTS OF THE EXCAVATED TRENCH SHALL BE BACKFILLED WITH 1/2"-3/4" CRUSHED AGGREGATE TO FINISHED GRADE. SEE STANDARD DRAWING NO. 205.
2. MINIMUM 36" COVER OVER PIPE REQUIRED
3. BASE SHALL BE PRECAST CONCRETE CONFORMING TO THE REQUIREMENTS OF ASTM C478.

CITY OF ALBANY, OREGON PUBLIC WORKS DEPARTMENT		
STANDARD SANITARY SEWER/ STORMDRAIN MAINLINE 24" MINI-MANHOLE CLEANOUT DETAIL		
NO SCALE	JULY 2019	NO. 416