



NOTES

1. WIRE ROPE TO BE 1/8" TO 3/16" STAINLESS STEEL, 7 STRANDS OF 19 WIRES.
2. SECURE GRATE IN PLACE WITH 54-INCHES OF WIRE ROPE. LOOP ENDS OF WIRE ROPE AROUND U-BOLT AND GRATE. CRIMP EACH END OF WIRE ROPE WITH 3" OVERLAP.
3. DRILL 2" DEEP HOLES INTO PIPE AND EPOXY #4 REBAR U-BOLT (2"X4") IN HOLES.
4. BEEHIVE GRATE: SEE STANDARD CONSTRUCTION SPECIFICATION.

CITY OF ALBANY, OREGON PUBLIC WORKS DEPARTMENT		
BEEHIVE OVERFLOW INLET GRATE		
NO SCALE	JANUARY 2015	NO. 620